

Executant 056 Biblioteca jud. O. Goga
 Obiectiv 0563 Refacere terasa etaj I
 Obiect 0563 Refacere terasa etaj I
 Categorie 05631 Refacere terasa etaj I

Deviz oferta

					[ron]
Pozitie	Cod resursa	U/M	Cantitate	Pret unitar	Valoare
Denumire resursa/ Corectii	Observatii				
0	1	2	3	4	5
1	CN11A	02 MP	35,0000		
VOPSITORII EXTERIOARE CU VOPSELE LAVABILE APLICATE PE TENCUIALA DRISCUITA					
2	RPCT09H1	82 M CUB	1,0000		
SPARGEREA PARTIALA CU MIJLOACE MEC SI MANUALA A ELEMENTELOR DE CONS.DIN BET.ARM.SI SIMPLU EXEC.FIN *					
3	RCSJ11B	02 MP	10,0000		
ASIM.TENCUIELI SPECIALE-PROTECTIE, LA ZID.CARAM./BETON					
3	999997	KG	225,0000		
MORTAR PENTRU REPARATII CU SETARE RAPIDA CONFORM SPECIFIC					
4	RPCU11A3	82 M	36,0000		
EXECUTAREA DE SANTURI CU SECTIUNE SUB 30CMP IN ZID ARIE DE BETON SAU PIATRA					
5	RCSU07D	02 M	36,0000		
MATARE SANTURI IN PERETI DE PANA LA 50CMP, DUPA INSTAL/CONSOLIDARI					
6	NL054	M	36,0000		
POZARE CABLURI					
7	CF10D1	82 MP	33,0000		
GLET DE IPSOS INCLUSIV STRAT DE AMORSA APLICAT IN DOUA STRATURI (EXTERIOR)					
8	RCSR08B	02 MP	33,0000		
ZUGRAVELI LAVABILE LA INT./EXT., 2STR., PE GLET DE IPSOS EXIST					
9	9999099	KG	22,0000		
VOPSEA LAVABILA					
10	RPEA15J1	82 M	36,0000		
DEMONTARE TUB PROT IPE INST APAR INTRE 36-40 MM*					
11	RPEF20F1	82 BUCATA	12,0000		
DEMONTARE CORP ILUMINAT FLUORESCENT*					
12	RPEF13A	99 BUCATA	12,0000		
MONTAREA CORPURILOR DE ILUMINAT DE					

Total fara T.V.A.
T.V.A.
TOTAL OFERTA

OFERTANT

Executant 056 Biblioteca jud. O. Goga
 Obiectiv 0563 Refacere terasa etaj I
 Obiect 0563 Refacere terasa etaj I
 Categorie 05631 Refacere terasa etaj I

Deviz analitic

Pozitie Corectii Denumire resursa Observatii Liste anexe	Cod resursa	U/M	Cantitate	Pret materiale Pret manopera Pret utilaj Pret transport Nr.ore/UM Greutate/UM	Val. materiale Val. manopera Val. utilaj Val. transport TOTAL A Greutate totala
0	1	2	3	4	5

1	CN11A	02	MP		35,00000
---	-------	----	----	--	----------

VOPSITORII EXTERIOARE CU VOPSELE LAVABILE APLICATE
 PE TENCUIALA DRISCUITA

L:LC68T -0001:7800859 -VOPSEA LAVABILA ACRILICA

2	RPCT09H1	82	M CUB		1,00000
---	----------	----	-------	--	---------

SPARGEREA PARTIALA CU MIJLOACE MEC SI MANUALA A EL
 EMENTELOR DE CONS.DIN BET.ARM.SI SIMPLU EXEC.FIN *

3	RCSJ11B	02	MP		10,00000
---	---------	----	----	--	----------

ASIM.TENCUIELI SPECIALE-PROTECTIE, LA ZID.CARAM./B
 ETON

3	999997		KG		225,00000
---	--------	--	----	--	-----------

MORTAR PENTRU REPARATII CU SETARE RAPIDA CONFORM S
 PECIF

4	RPCU11A3	82	M		36,00000
---	----------	----	---	--	----------

EXECUTAREA DE SANTURI CU SECTIUNE SUB 30CMP IN ZID
 ARIE DE BETON SAU PIATRA

5	RCSU07D	02	M		36,00000
---	---------	----	---	--	----------

MATARE SANTURI IN PERETI DE PANA LA 50CMP, DUPA IN
 STAL/CONSOLIDARI

6	NL054		M		36,00000
---	-------	--	---	--	----------

POZARE CABLURI

7	CF10D1	82	MP		33,00000
---	--------	----	----	--	----------

GLET DE IPSOS INCLUSIV STRAT DE AMORSA APLICAT IN
 DOUA STRATURI (EXTERIOR)

Executant056 Obiectiv0563 Obi0563 Cate05631

0	1	2	3	4	5
----------	----------	----------	----------	----------	----------

8 RCSR08B 02 MP 33,00000

ZUGRAVELI LAVABILE LA INT./EXT., 2STR., PE GLET D
E IPSOS EXIST

9 9999099 KG 22,00000

VOPSEA LAVABILA

10 RPEA15J1 82 M 36,00000

DEMONTARE TUB PROT IPE INST APAR INTRE 36-40 MM*

11 RPEF20F1 82 BUCATA 12,00000

DEMONTARE CORP ILUMINAT FLUORESCENT*

12 RPEF13A 99 BUCATA 12,00000

MONTAREA CORPURILOR DE ILUMINAT DE

Greutate 2,551
Total ore 242,00

OFERTANT

Executant 056 Biblioteca jud. O. Goga
 Obiectiv 0563 Refacere terasa etaj I
 Obiect 0563 Refacere terasa etaj I
 Categorie 05631 Refacere terasa etaj I

Recapitulatie

[ron]

	Material	Manopera	Utilaj	Transport	TOTAL
	M	m	U	t	T
Cheltuieli directe					
Alte cheltuieli directe					
Contr. asig. de munca	%				
	Mo	mo	Uo	to	To
TOTAL CHELT. DIRECTE					
Cheltuieli indirecte	Io =	% x To			
Profit	Po =	% x (To+Io)			
TOTAL GENERAL pe categorie	Vo = To+Io+Po				

OFERTANT